WATER-SUPPLY DIVISION.

Dated 13th June 1916.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Water-Supply Division, up to 12 noon of the 3rd July 1916, for constructing an elevated tank at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1917.

2. The plans, detailed estimates and conditions may be seen in the Sanitary Engineer's Office, between the hours 11 A.M. to 5 P.M., on all working days.

3. Tenders should be submitted on proper printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an elevated tank at Shimoga," in default of which, tenders will be rejected.

5. The final acceptance of the tender will rest with the Southern Circle Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and the earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. An abstract estimate for constructing an elevated tank is given below :—

No.	Items of work	Per	Quantity	
			Groundfloor	First floor
1	Earthwork excavation	Cyd.	212	...
2	Surki concrete	Cft.	1,910	...
3	Surki concrete for filling above ground arches	"	1,361	...
4	Burnt brick in surki mortar	"	10,253	...
5	Do do	"	...	7,878
6	Burnt brick in surki mortar for arches	"	4,491	...
7	Do do	"	...	106
8	Plastering with surki mortar	Sqr.	62·24	...
9	Do do	"	...	18·48
10	Cornice	Rft.	180	...
11	Do	"	...	156
12	Parapet wall including pedestal and plastering	"	...	152
13	Perforated zinc sheet ventilators	Each	...	8
14	Iron ladder	L. S.	L. S.	L. S.
15	Drainage pipes	"	...	"
16	Terracing with jack arch	Sqr.	...	12·42
17	Cement plastering, ½" thick	"	...	18·75
18	Constructing valve cisterns	Each	3	
19	Clearing site	Item	L. S.	

JOHN BHORE,
Sanitary Engineer.

BANGALORE DIVISION.

Notification dated 17th June 1916.

Grass grown in the catchment area of Saukey's Reservoir, Bangalore, will be sold by public auction on Saturday the 8th July 1916 at 8 A.M., at the tank site by the Assistant Engineer, Headquarters Range, Bangalore.

The highest bidder will have to pay one-fourth of the amount at once and the balance within a week from the date of auction, failing which the produce will be re-auctioned and the difference in the amount of realization will be recovered from the original purchaser.

The lease is for one year only to the 30th June 1917.

C. VIJAYARANGAM NAIDU,
Executive Engineer.